

ZESTAWIENIE MATERIAŁÓW - ELEMENTY ŻELBETOWE
(ROZBUDOWA I PRZEBUDOWA BUDYNKU PRZEDSZKOLA W KANIOWIE)

SEGMENT E					
ELEMENT	STAL ZBROJENIOWA [kg]				BETON [m3]
	Ø6 mm	#10 mm	#12 mm	#16 mm	
PŁ.E-1		767,31			11,44
PŁ.E-2	15,35	285,20			3,45
PŁ.E-3	8,04	159,96			1,81
PŁ.E-4	8,86	105,71	17,80		1,08
PŁ.E-5	6,20	24,80	14,24		0,56
B.E-1	17,16		59,27		1,23
B.E-2	3,72		11,57		0,27
B.E-3	13,28		43,08		1,17
N.E-1	1,69		4,98		0,11
W.E-1	10,65		34,46		0,66
W.E-2	20,68		55,22		1,97
S.E-1	25,87		69,78		1,76
Ł.E-1	91,52		97,19	369,72	14,59
Ł.E-2	42,47		43,73	166,37	7,29
Ł.E-3	48,40			229,42	6,60
SUMA	313,89	1 342,98	451,32	765,51	53,99

SEGMENT F					
ELEMENT	STAL ZBROJENIOWA [kg]				BETON [m3]
	Ø6 mm	#10 mm	#12 mm	#16 mm	
N.F-1	3,87		11,39		0,24
N.F-2	3,27		9,61		0,20
N.F-3	5,63		16,55		0,35
N.F-4	5,93		26,17		0,37
W.F-1	67,52		327,77		4,19
W.F-2	17,55		127,76		2,48
W.F-3	50,34		162,91		3,12
W.F-4	4,24		13,71		0,26
R.F-1	34,32		111,07		2,34
R.F-2	2,38		10,68		0,16
Ł.F-1	247,46		262,78	999,67	39,44
Ł.F-2	140,80			667,39	19,20
SC.F-1	26,78		210,29		8,32
SUMA	610,06	-	1 290,69	1 667,06	80,67

SEGMENT A, B, C					
ELEMENT	STAL ZBROJENIOWA [kg]				BETON [m3]
	Ø6 mm	#10 mm	#12 mm	#16 mm	
PŁ-1		186,00			1,61
PŁ-2		55,80			0,67
PŁ-3		186,00			1,61
PŁ-4		55,80			0,67
B-1	6,58		24,56		0,48
B-2	4,43		16,55		0,33
B-3	6,58		24,56		0,48
F-1	4,29		13,88		0,35
SUMA	21,88	483,60	79,57	-	6,21

SUMA CAŁ.	945,83	1 826,58	1 821,57	2 432,57	140,87
------------------	--------	----------	----------	----------	--------